

Deep Drift: saved versions and how git works

A guide for Hasib. Keeps track of every saved version of the dive, and explains how to go back to one.
Updated 27 Sep 2026.

In one sentence: git is a program that takes a photo of the whole project each time we save (a *commit*), keeps every photo forever, and can put any old photo back. Before each realism change we have a safe copy to return to.

1. Where everything is

Git program	<code>C:\Program Files\Git\cmd\git.exe</code> (the one Windows uses) <code>C:\Program Files\Git\mingw64\bin\git.exe</code> (the same program, used inside the Git Bash window)
Git version	git version 2.54.0.windows.1
The project	<code>C:\Users\hasib\Downloads\deep-drift-project</code>
The history	<code>C:\Users\hasib\Downloads\deep-drift-project\.git</code> A hidden folder, about 10.3 MB. Every saved version lives inside it (packed and compressed). Never edit or delete it: deleting it deletes all history. Your normal files are not affected.
Settings for this project	<code>.git\config</code> . Name <code>Hasib</code> , email <code>hasibahmad.njupt@gmail.com</code> . These are set for this project only. Git on this computer has no global name or email.
Branches	<code>main</code> : released versions. <code>feature/faster-opening</code> , <code>feature/start-screen</code> , <code>feature/v1.2-continuous-dive</code> , <code>feature/v1.3-solid-and-smooth</code> , <code>feature/v1.4-feel</code> , <code>feature/v1.5-controls</code> : where each version was built (kept for the record). You are on <code>feature/faster-opening</code> . See section 4.
Run it locally	In the project folder: <code>node tools/serve.mjs</code> , then open <code>http://localhost:8080</code> . Stop it with Ctrl+C.
Tags (named versions)	<code>v1.0</code> , <code>v1.1</code> , <code>v1.2</code> , <code>v1.3</code> , <code>v1.4</code> , <code>v1.5</code> , <code>v1.5.1</code>
Online copy	origin <code>https://github.com/hasibahmad1995/deep-drift.git</code> (fetch) origin <code>https://github.com/hasibahmad1995/deep-drift.git</code> (push)
Plain backup page	<code>backup\deep-drift-v1.0.html</code> . Double-click it to play the v1.0 dive. No git needed. (Any other version: see section 5.)
This guide	<code>docs\git-tracking.pdf</code> , made by <code>docs\make_git_tracking.py</code>
Special files	<code>.gitignore</code> : things git ignores (<code>node_modules</code> , screenshots <code>*.png</code> , <code>__pycache__</code>). <code>.gitattributes</code> : keeps line endings exactly as saved. Without it, Windows git would switch them when restoring, so an old version would not come back byte for byte.

2. Why the version is called v1.0, and how numbers go up


The project file `package.json` said `0.4.0` before git was set up. A number starting with 0 usually means "still being built". You chose to call the current dive **v1.0**: the first saved version. `package.json` was changed to `1.0.0` so everything agrees.

The rule from now on (**vMAJOR.MINOR**, plus a third number for small fixes):

- **MINOR goes up by one** for each finished, tested change to the dive: v1.1 (the realism work), v1.2 (the continuous dive), and so on. After v1.9 comes v1.10, not v2.0.
- **MAJOR goes up** (v2.0) only for a very big change you decide on, for example a full redesign.
- **The third number goes up** for a set of small improvements, like v1.5.1 (a new start screen, a button moved, music quiet at home). A single tiny change does not need a number at all: it is still a saved commit you can go back to.
- **No new number** for commits that do not change the dive: this guide, test fixes, notes. They still get a row in the table, with "none" as the version.
- If a version is undone, its number is **not reused**. The next change takes the next number, so a number always means one thing.

3. How git works

The three places a change passes through



1. **Working folder.** The files as they are now. When code is edited, only this changes. Git notices, but nothing is saved yet.
2. **Staging area.** `git add` puts chosen changes here. It is a waiting list for the next save, so one save can hold one tidy change even if other files were also touched.
3. **History.** `git commit` seals everything on the waiting list into a new saved version inside `.git`. After that it is safe: later edits cannot damage it.

What a commit is


A commit is a complete snapshot of every tracked file at that moment, plus a message (what and why), the author, the date, and a pointer to the commit before it. Git stores only what changed, so saving often is cheap: the whole history today is about 10.3 MB.

Each commit gets an **ID** like `7929f37` (short form) or a 40-character long form. The ID is a fingerprint calculated from the commit's content. Change one letter anywhere and the ID changes completely. That is why an old

version cannot be changed quietly. It is also why this file cannot show the ID of the commit that contains it: the ID is only known after the file is saved. That row is filled in at the next update.

History, branch, tag and HEAD

side branches: feature/... (one per version, where it was built)



Read left to right, row after row. Lower line: main (released versions). Upper line: side branches.

- **History** is a chain: every commit points back to its parent.
- **Branch:** a name that points at the newest commit of a line of work and moves forward with every commit. `main` holds the released versions; each new version is built on its own side branch first (the upper row).
- **Tag** (`v1.0`): a permanent name for one commit. It never moves. This is how "go back to v1.1" stays easy.

- **HEAD:** "where you are now", the version the working folder is based on. Normally HEAD is on `main`.

4. Branches, testing and releases (how each version is made)

Since v1.2 each version is built the way software teams do it (a simple "SDLC": build, test, release):

1. **Branch.** Start a side branch for the version, for example `git switch -c feature/v1.6-behaviour`. `main` is not touched, so the last released version is always safe there.
2. **Build in small steps**, each saved as its own commit on the branch (for v1.2: refactor, engine upgrade, the continuous dive). The code is split into small files, one job each, so every part can be found and changed later.
3. **Test locally** after every step: `node tools/serve.mjs` to play it at `http://localhost:8080`, and the test scripts (`tests\shot.py`, `ui.py`, `live.py`, `glide.py`, `solid.py`, `startup.py`, `life.py`, `controls.py`).
4. **Show Hasib** before and after. Only if it looks better and nothing broke:
5. **Release.** Set the version in `package.json`, merge the branch into `main` with a merge commit (`git switch main` then `git merge --no-ff feature/...`), and tag it (`git tag -a v1.3 -m "..."`).
6. **Report:** after every fix, a PDF report of what is on the website and what to do next (`python docs/make_report.py`, into `docs/reports`).
7. **Record it:** add rows to `COMMITs` in `docs\make_git_tracking.py`, run it, and commit the new PDF.
8. **Publish** (later): `python tools\build.py` makes `dist\` with only the files a visitor needs; that folder goes to the host.

If a step looks worse or breaks something, it is not committed; the files are put back with `git restore`. If a problem is found only later, that one commit is undone with `git revert` (below), and the table shows it as "Undone". A whole branch can also simply be left unmerged: `main` never saw it.

5. How to look back and go back

Type these in **Git Bash** (Start menu, "Git Bash") or in PowerShell, after moving into the project folder: `cd C:\Users\hasib\Downloads\deep-drift-project`. Or ask Claude to do it.

<code>git log --online --decorate</code>	List every saved version, newest first, with IDs and tags.
<code>git log --online --graph --all</code>	The same, drawn with the branches and merges.
<code>git status</code>	Show which files changed since the last save. Safe, changes nothing.
<code>git diff</code>	Show the exact lines changed since the last save. Safe.
<code>git show v1.1:dist/index.html > old.html</code>	v1.0 and v1.1 were one single file: this saves one as <code>old.html</code> , without touching the project. Open it in a browser.
<code>git switch --detach v1.2</code> <code>node tools/serve.mjs</code> then <code>git switch main</code>	Play any version from v1.2 on: the folder turns into that version, the server runs it, and the last command comes back to the newest. Nothing is lost. (Save or undo current edits first; git will warn you.)

```
git restore src/world.js
```

Throw away unsaved edits to one file, back to the last commit.

```
git revert 1a2b3c4
```

Undo one commit by adding a new commit that does the opposite. Later changes are kept, and the history still shows what happened. **The safe way to undo.**

Careful: `git reset --hard v1.0` makes the project exactly v1.0 and **deletes unsaved edits and every commit after it** (tagged versions can still be recovered, others are hard to find). Use `git revert` or `git switch` instead, or ask Claude first.

6. The table of saved versions

Every commit, oldest first. The commit ID links a row to git: `git show 7929f37` shows everything in that commit.

#	Version	Commit ID	Date	Commit name	Detailed description	Status
1	v1.0	159e389	24 Sep 2026, 18:22	Save the dive as it was before the realism work v1.0: save the dive as it was before the realism work	What changed: Nothing in the dive itself was changed. The whole project was put under git for the first time, so every later change can be undone. Files: - All of <code>src/</code>, <code>assets/</code>, <code>tests/</code>, <code>tools/</code>, <code>README.md</code>, <code>CLAUDE.md</code>, <code>build.py</code>, <code>.gitignore</code> <code>dist/index.html</code> : the built, playable page <code>package.json</code> : version changed from 0.4.0 to 1.0.0 - New: <code>backup/deep-drift-v1.0.html</code> , a plain copy of the page that opens without git - New: <code>.gitattributes</code> , keeps line endings exactly as saved State of the dive: Six places: reef, open ocean, midnight, vents, wreck, trench. One real 3D model (the barramundi fish); everything else is built by code. The weak spots listed in <code>CLAUDE.md</code> (hazy reef wall, dark wreck and trench, small deep animals, corals you can swim through, untested on phones) are all still present. Checks: All five scripts pass a syntax check, alone and joined. <code>dist/index.html</code> is identical to a fresh build. No screenshots yet: the test tools were not installed at this point.	Kept
2	none	fa9e4ca	24 Sep 2026, 18:25	Add this git tracking guide docs: add the git tracking guide	What changed: Added this PDF and the small script that makes it. The dive was not changed, so this commit gets no version number. Files: - New: <code>docs/git-tracking.pdf</code> (this file) - New: <code>docs/make_git_tracking.py</code> (writes this file; holds the table entries) State of the dive: Same as v1.0. Checks: PDF opened and read through.	Kept

#	Version	Commit ID	Date	Commit name	Detailed description	Status
3	none	2bc92ac	24 Sep 2026, 18:35	Make the tests work on Windows and apply the page policy for real tests: make the test tools work on Windows and apply the page policy for real	What changed: The screenshot tests were meant to run under a strict page policy like the real host, but the policy was never applied: it only matched an old file name, and the test browser cannot add it to file:// pages anyway. The page is now served from a made-up web address that the test script answers itself, so the policy really applies and anything not allowed is blocked. Screenshots go to <code>tests/out/</code> instead of <code>/tmp</code>, which does not exist on Windows. <code>build.py</code> now reads and writes UTF-8 and keeps line endings, so the built page is byte for byte the same. Files: <code>tests/shot.py</code>, <code>tests/ui.py</code>, <code>tests/live.py</code>, <code>tests/grid.py</code> <code>build.py</code>, <code>.gitignore</code> (ignores <code>tests/out/</code>) <code>CLAUDE.md</code>: how to install the test tools on Windows (the full npm install fails on <code>sharp</code>, which only the old fish-model tools need, so only <code>three.js</code> is fetched) State of the dive: Same as v1.0. First real screenshots taken: the "before" pictures in section 7. Checks: Screenshots at 9 dive moments under the strict policy, no page errors. The real fish model still loads under the policy.	Kept
4	none	df2af88	24 Sep 2026, 19:21	Tests: wait for the Begin button without eval tests: wait for the Begin button without eval	What changed: Once the strict policy really applied, one test helper (<code>wait_for_function</code>) broke, because it runs text as code and the policy forbids that. The tests now wait with <code>wait_for_selector</code>, which the policy allows. Found while testing v1.1. Files: <code>tests/shot.py</code>, <code>tests/ui.py</code>, <code>tests/live.py</code> State of the dive: Same as v1.0. Checks: All three test scripts run with no errors.	Kept

#	Version	Commit ID	Date	Commit name	Detailed description	Status
5	v1.1	4eec30b	24 Sep 2026, 19:21	A more realistic reef wall, wreck, trench and deep animals v1.1: a more realistic reef wall, wreck, trench and deep animals	What changed: Hasib asked for the four areas in one version. Reef wall: rock grain painted from three directions (never stretched) that catches the light like real bumps; ledges, deep cracks and lumpy rock; more colour from encrusting life; a new set of corals and sponges growing out of the wall (vase and tube sponges, sea fans, soft and plate corals, sea whips). Wreck: rebuilt as a 47 m steamship: keel, flat sides, raked bow, flat stern, plate seams, black and faded red paint, rotted plank deck with holes, deckhouse with windows and bridge, broken railings, davits, a snapped mast across the deck, hatches, a torn hole in the side; rusticles hanging with gravity (as on the Titanic, at the same depth), anchor chain, sponges and anemones on deck, a debris field with the fallen funnel. Trench: finer walls with rock layers and ledges, pale sediment on ledges, boulders at the foot of the walls, sea cucumbers on the floor; the dive ends about 7 m above the floor. Deep light: the deep water was set so murky you could see only about 8 m; it is now clear, as real deep water is, and a soft lamp moves with the diver. Deep animals: tube worms thicker and in dense clumps with red plumes; anglerfish dark with fangs and a blue-green lure, now in view about 9 s instead of half a second; dumbo octopus with webbed arms; snailfish passing close, plus a group feeding near the trench floor; shrimp shapes for vent shrimp and amphipods. Speed: only the current place is drawn, so the deep places cost about a quarter of v1.0; the reef costs the same as v1.0. Files: <code>src/core.js</code> : rock grain, bumps, rust and rock layers in <code>wet()</code> ; clearer deep water; lamp; softer torch <code>src/world.js</code> : reef wall and wall corals, new sponges, <code>buildShip</code> , <code>addRusticles</code> , debris field, trench walls, boulders, sea cucumbers, tube worms <code>src/life.js</code> : dumbo web, anglerfish teeth and colour, <code>shrimpGeo</code> , paler animals toned down <code>src/run.js</code> : animals that sink with the diver, dumbo and snailfish routes, lure light, trench path, drawing only the current place <code>dist/index.html</code> rebuilt; <code>package.json</code> 1.1.0; <code>CLAUDE.md</code> updated State of the dive: See the before and after pictures in section 7. Still to do: corals are not solid, phone	Kept

#	Version	Commit ID	Date	Commit name	Detailed description	Status
					testing, anglerfish teeth are too small to notice, trench rock layers are subtle. Checks: Syntax of all scripts; screenshots at 9 dive moments under the strict page policy; phone and desktop menu test; live play test (pause, restart, music). No page errors. Triangles per frame measured at 1300x800 against v1.0: reef 4.2 million (v1.0: 4.0), deep places about 1.0 million (v1.0: 4.0).	
6	none	593c8f5	24 Sep 2026, 19:23	Update this guide for v1.1 docs: update the tracking guide for v1.1	What changed: Added the four new commits to this table, before and after pictures (section 7), and a history diagram drawn from the real commits. Files: - docs/git-tracking.pdf , docs/make_git_tracking.py - New: docs/img/before-v1.1.jpg and docs/img/after-v1.1.jpg State of the dive: Same as v1.1. Checks: PDF opened and read through.	Kept

#	Version	Commit ID	Date	Commit name	Detailed description	Status
7	none	fb31bb2	24 Sep 2026, 21:14	Split the code into small modules; run the site locally refactor: split the code into small ES modules and run the site locally	What changed: Hasib asked for clean, separated code that can be found later, and for local testing before shipping. The five big script files (about 2,400 lines) became 55 small modules, one job each, in folders by area (engine, dive, world, life, diver, ui, audio, content). The page is a normal folder now: index.html, styles/, src/, and three.js and the fonts included in the project, so nothing is loaded from other websites. A small local server (<code>node tools/serve.mjs</code>) runs it at <code>http://localhost:8080</code>. The dive itself did not change: screenshots at 9 moments looked the same as v1.1. Files: • New folders <code>src/engine</code> , <code>src/dive</code> , <code>src/world</code> , <code>src/life</code> , <code>src/diver</code> , <code>src/ui</code> , <code>src/audio</code> , <code>src/content</code> , <code>src/util</code> • <code>index.html</code> , <code>styles/</code> , <code>vendor/three/</code> , <code>assets/fonts/</code> • <code>tools/serve.mjs</code> (local server), <code>tools/build.py</code> (makes <code>dist/</code> for publishing), <code>tools/vendor_three.py</code> • Removed: the old single-file build; <code>dist/</code> is no longer kept in git State of the dive: Same as v1.1. Checks: Screenshots at 9 moments, menus on phone and desktop, live play. A first Python server dropped requests on Windows and the page could hang while loading; the Node server loaded 6 of 6 times in about 2 s.	Kept

#	Version	Commit ID	Date	Commit name	Detailed description	Status
8	none	4197c3b	24 Sep 2026, 22:59	Upgrade the 3D engine to the current three.js engine: upgrade three.js from r128 (2021) to r186	What changed: three.js r128 (2021) became r186. This turns on modern colour management and physically based lights (light fades with distance, as in reality), the base for more realistic pictures. Strengths were converted so the dive looked the same. One bug found on the way: the new engine gives its fog colour already converted for the screen, which made every deep place flat bright blue; our fog now keeps its own colour. Files: • vendor/three/ (r186), tools/vendor_three.py • src/engine/ lights, environment, uniforms and wet.js ; small renames in several shaders State of the dive: Same as v1.1, on the new engine. Checks: Screenshots at 9 moments matched v1.1; menus and live play pass.	Kept

#	Version	Commit ID	Date	Commit name	Detailed description	Status
9	none	10cb423	25 Sep 2026, 00:01	One continuous dive, gliding swim, life at real depths dive: one continuous 7-minute dive from the surface to the Challenger Deep	What changed: Hasib found the jumps between places jarring and wanted more to explore, kept real. One world: the dive now goes down the side of a volcanic island without any fade or depth jump: reef, the island cliff into the twilight and midnight zones, a vent terrace at ~1,600 m, the volcano slope, the abyssal plain with the wreck at ~5,000 m, the trench wall, and the floor of the Challenger Deep at 10,935 m. Swimming: no button. You drift toward wherever you look and are always sinking; looking up slows the sinking, looking down speeds it up; you can never swim back up, so you must aim early; a gentle current brings you back if you stray too far. Life at real depths: every animal only appears where it really lives (for example snailfish only between about 6,500 and 8,300 m). New: deep reef (sea fans, black corals, sponges), hatchetfish, vampire squid, gulper eel, grenadiers, tripod fish, bamboo corals, glass sponges, sea lilies, brittle stars, sea pigs, xenophyophores, manganese nodules, liquid CO2 droplets at the vents. Look: backscatter (specks lit in the torch beam, like real deep-sea footage), fog that melts into the background, realistic rock brightness. Honest page text: the places are moved closer together and the descent is sped up. Files: - New: <code>src/dive/depth.js</code>, <code>route.js</code>; <code>src/world/sites.js</code>, <code>terrain.js</code>, <code>benthos.js</code>, <code>culling.js</code>; <code>src/diver/glide.js</code>; <code>src/life/species-deep.js</code>, <code>cast-deep.js</code>; <code>tests/glide.py</code> - Changed: vents, wreck, trench, reef, corals, collision, camera, input, cast, extras, passers, facts, HUD, particles, page text, README, CLAUDE.md - Removed: <code>src/dive/timeline.js</code>, <code>src/dive/path.js</code> (the old six separate places) State of the dive: One continuous ~7 minute dive from the surface to 10,935 m. See the pictures in section 7. Checks: Screenshots down the whole dive under the strict page policy; menus on phone and desktop; live play; glide test (steers, never rises, sinks slower or faster, roaming limit). No page errors. Triangles per frame at 1300x800: reef about 4.7 million (v1.1: 4.2), open water 0.8 million, deep places 1.1 to 2.2 million.	Kept

#	Version	Commit ID	Date	Commit name	Detailed description	Status
10	none	0e6fb86	25 Sep 2026, 00:01	Set the version number to 1.2.0 release: set the version to 1.2.0	What changed: The last step on the branch before merging: <code>package.json</code> says 1.2.0. Files: <code>package.json</code> State of the dive: Same as the commit before. Checks: None needed.	Kept
11	v1.2	42dfe05	25 Sep 2026, 00:01	Release v1.2: merge the branch into main v1.2: one continuous dive to the Challenger Deep, glide swimming, life at real depths	What changed: The merge commit that brings the four commits of <code>feature/v1.2-continuous-dive</code> into <code>main</code>, tagged <code>v1.2</code>. From here, <code>main</code> is the v1.2 dive. Files: Everything changed on the branch (the four rows above it). State of the dive: v1.2: one continuous dive to the Challenger Deep with gliding swim and life at real depths. Checks: All tests passed on the branch before merging.	Kept
12	none	1f3e0b2	25 Sep 2026, 00:05	Update this guide for v1.2 docs: update the tracking guide for v1.2	What changed: New rows, a history diagram that shows the branch and the merge, a new part explaining branches and releases (section 4), before and after pictures for v1.2, and the plan for v1.3 and later. Files: <code>docs/git-tracking.pdf</code>, <code>docs/make_git_tracking.py</code> - New: <code>docs/img/before-v1.2.jpg</code>, <code>docs/img/after-v1.2.jpg</code> State of the dive: Same as v1.2. Checks: PDF opened and read through.	Kept

#	Version	Commit ID	Date	Commit name	Detailed description	Status
13	none	7987b4e	25 Sep 2026, 20:44	Open faster; no freezes at the start of the dive perf: open faster and stop freezes early in the dive	What changed: Hasib noticed lag when the page opens. Measured first (a new test, <code>tests/startup.py</code>), then fixed four causes. 1. Too much drawn: each kind of coral was one big batch covering the whole reef, so all 3.9 million reef triangles were drawn every frame, even behind you. Corals, sea-floor life, rocks, tube worms, nodules and sea cucumbers are now split into tiles, and only tiles on screen and within sight are drawn. Small corals shrink away smoothly with distance (when they are a few pixels across and already faded) instead of being drawn out to 250 m. Schools of fish are skipped when off screen or far away. The first view went from 4.7 million to 0.34 million triangles. 2. Drawing while loading: the page drew the half-built world between loading steps. Now it builds in steps with a progress message (for example: Loading the coral reef... 11%) and draws nothing until it is ready. 3. Shaders built during the dive: the first time a material is drawn, the browser builds its shader, a freeze each time. All are now built before Begin (<code>warmup.js</code>). 4. A hidden light: the anglerfish carries a light; hiding and showing it made three.js rebuild the shaders of everything on screen. The light now stays and just goes dark. Also: picture sharpness now drops quickly when frames are slow and rises back slowly (<code>quality.js</code>), and tiny point sprites keep their size when it changes (an old bug). Files: - New: <code>src/util/steps.js</code>, <code>src/engine/warmup.js</code>, <code>src/engine/quality.js</code>, <code>src/world/tiles.js</code>, <code>tests/startup.py</code> - Changed: <code>main.js</code>, <code>culling.js</code>, <code>corals.js</code>, <code>benthos.js</code>, <code>floor.js</code>, <code>vents.js</code>, <code>wreck.js</code>, <code>trench.js</code>, <code>school.js</code>, <code>cast.js</code>, <code>wet.js</code> (new option <code>shrink</code>), <code>lights.js</code>, particles, bubbles, effects State of the dive: Same dive, lighter to draw. See the chart in section 7. Checks: In the test browser: Begin ready after 2.5 s (v1.2: 5.4 s); 26 pictures in the first 6 s of the dive (v1.2: 9); no shader built after the warm-up. Screenshots looked the same as v1.2.	Kept

#	Version	Commit ID	Date	Commit name	Detailed description	Status
14	none	bcd1382	25 Sep 2026, 21:03	Nothing passes through the diver; nothing pops in or out feat: a solid world, animals that give way, nothing pops in or out	What changed: Hasib's two rules: you cannot pass through anything (animals move away, or you are stopped), and nothing appears or vanishes suddenly. Solid world: corals, sponges, bamboo corals, sea lilies, big rocks, tube worm clumps, the wreck's masts, railings, winches, funnel and boiler, and the whale bones are now solid (7,794 simple shapes kept in a grid, <code>solids.js</code>). The diver is a 0.45 m ball and slides around them. The wreck is checked with its real hull shape instead of one big box. Animals give way: each animal senses the diver's body and has its own comfort distance. Too close, it speeds up smoothly and swims aside. If it still touches you, a light animal is pushed aside, and a heavy one (whales, the whale shark, the manta) pushes you aside instead. School fish keep about 1.4 m away and part around you. No pops: passing animals start where you cannot see them (off screen or lost in the water), swim across, and leave only once out of sight again; their path never goes through rock. Glows (vents, anglerfish lure) fade with distance. Deep animals that sink with you slow down gently instead of stopping dead. Bugs found by the new test and fixed: animals more than 300 m away stopped moving for good (so after the dive restarted they were frozen and hidden); near the top of the reef wall the diver could be lifted 58 m in one frame; past the look-up limit the diver was pulled down 6 m in one frame; the reef collision stepped up to 2 m at once; the lifeboat arms on the wreck were never added (their code was inside a comment). Files: - New: <code>src/world/solids.js</code>, <code>tests/solid.py</code> - Changed: <code>collision.js</code>, <code>glide.js</code>, <code>touch.js</code>, <code>school.js</code>, <code>passers.js</code>, <code>motion.js</code>, <code>main.js</code>, <code>ship.js</code>, <code>wreck.js</code>, <code>corals.js</code>, <code>benthos.js</code>, <code>floor.js</code>, <code>vents.js</code>, <code>effects.js</code>, <code>debug.js</code> State of the dive: The world is solid, animals give way, nothing pops. See the whale skeleton pictures in section 7. Checks: <code>tests/solid.py</code> simulates the whole dive plus a reef run and a wreck run (10,900 steps): 0 times inside something solid, 0 animal or fish overlaps, 0 pops, 0 jumps. Direct contact: a whale shark pushed the diver 1.9 m aside; a jellyfish was nudged 0.7 m away. Glide, menu and live tests pass.	Kept

#	Version	Commit ID	Date	Commit name	Detailed description	Status
15	none	df0bc04	25 Sep 2026, 21:11	Describe v1.3 for the next person (and for Claude) docs: describe v1.3 in CLAUDE.md and README	What changed: How the solid world, tiles, warm-up, sharpness control, giving way and passers work; the rule never to hide a light; the two new tests; the plan moved on (animal behaviour is now v1.4, real models v1.5 and later). Files: CLAUDE.md , README.md State of the dive: Same as the commit before. Checks: Read through; no em dashes.	Kept
16	none	32cda40	25 Sep 2026, 21:11	Set the version number to 1.3.0 release: set the version to 1.3.0	What changed: The last step on the branch before merging: package.json says 1.3.0. Files: package.json State of the dive: Same as the commit before. Checks: None needed.	Kept
17	v1.3	bbdc609	25 Sep 2026, 21:11	Release v1.3: merge the branch into main v1.3: a solid world, smooth arrivals and a faster start	What changed: The merge commit that brings the four commits of feature/v1.3-solid-and-smooth into main , tagged v1.3 . Why 1.3 and not 2.0: it is the same dive, it just behaves more like the real thing and opens faster. A 2.0 would mean a big change in what the dive is (for example real 3D models everywhere). Files: Everything changed on the branch (the four rows above it). State of the dive: v1.3: nothing passes through the diver, nothing pops in or out, faster opening. Checks: All tests passed on the branch before merging.	Kept
18	none	aaca2f4	25 Sep 2026, 21:13	Update this guide for v1.3 docs: update the tracking guide for v1.3	What changed: New rows, the whale skeleton before and after pictures, the opening chart, and the plan for v1.4 and later. Files: - docs/git-tracking.pdf , docs/make_git_tracking.py - New: docs/img/solid-v1.3.jpg , docs/img/opening-v1.3.jpg State of the dive: Same as v1.3. Checks: PDF opened and read through.	Kept

#	Version	Commit ID	Date	Commit name	Detailed description	Status
19	none	b8ec339	25 Sep 2026, 23:52	A smooth start on Hasib's laptop; no blink at Begin perf: a smooth start on laptop graphics, no blink at Begin	What changed: Hasib saw the camera blink and lag at the beginning. This time it was measured on his laptop's own graphics card (Intel UHD, screen 1536x864 at 125%), not only the slow test graphics. The reef, the start of the dive, took 50 to 70 ms per picture; after a few seconds the automatic sharpness dropped, which cleared the picture for a frame (a blink) and caused a 170 to 200 ms hitch; and Begin cut the picture to black. Now: before Begin the page draws the reef a few times and picks the sharpness for about 30 ms per picture (<code>benchmark.js</code>); sharpness changes only after about a second of slow pictures and never between drawing and showing; no edge smoothing on scaled screens (a fifth of the cost there); cheaper rock grain; coral shapes share their corners; the warm-up copies shapes a few at a time so loading never freezes long; Begin fades the intro card away over the live picture. Files: - New: <code>src/engine/benchmark.js</code> , <code>src/lib/geometry-utils.js</code> - Changed: <code>renderer.js</code> , <code>quality.js</code> , <code>warmup.js</code> , <code>wet.js</code> , <code>corals.js</code> , <code>styles/main.css</code> , <code>tests/startup.py</code> (new options <code>--gpu</code> , <code>--screen</code> , <code>--freeze</code>) State of the dive: Smooth from the first second on Hasib's laptop, a little softer picture there. Checks: On the real graphics card at Hasib's size: first 8 to 12 s of the dive at 60 pictures a second, no hitch over 33 ms (v1.3: 200 ms), no sharpness change during the dive, longest loading freeze 0.37 s (v1.3: 1.85 s).	Kept

#	Version	Commit ID	Date	Commit name	Detailed description	Status
20	none	f351714	25 Sep 2026, 23:52	Living pause, a new dive every time, smooth arrow keys, real fish speeds feat: hover while the sea lives on, a new dive every time, smooth keys, lively schools	What changed: Pause: it now stops only the diver; the sea has its own clock, so schools, sharks and jellyfish keep swimming, passing animals swim on, and new visitors still come. Variety: at Begin and every restart each scripted animal rolls its version: earlier or later, nearer or farther, either side, faster or slower, and about one dive in seven not there; circling animals and schools start anywhere and may circle the other way; the dolphins stay one pod. Every version is checked against rock with a new honest 0.5 m check; if none is clear the animal stays away. This found older mistakes: the three reef sharks circled through the reef wall and the manta met you inside the wall (it now glides over you). Keys: arrow keys speed up to a smooth turn and ease to a stop instead of 7-degree jumps. Fish: each tail beat moves a fish about 0.7 of its length (Bainbridge 1958), so small school fish now beat their tails about 8 times a second instead of 2; schools surge (speed up and slow down by about 40%); each fish faces its real movement. Files: - New: <code>src/life/variety.js</code> , <code>tests/life.py</code> - Changed: <code>main.js</code> , <code>state.js</code> , <code>camera.js</code> , <code>input.js</code> , <code>collision.js</code> (new <code>inRock</code> for animals), <code>motion.js</code> , <code>school.js</code> , <code>passers.js</code> , <code>touch.js</code> , <code>cast.js</code> , <code>cast-deep.js</code> , <code>extras.js</code> , <code>small-shapes.js</code> , <code>barramundi.js</code> , <code>hud.js</code> , <code>playback.js</code> , <code>debug.js</code> , <code>tests/solid.py</code> State of the dive: Pause hovers while the sea lives on; every dive differs; smooth keys; lively schools. Checks: <code>tests/life.py</code> : 3 s of pause, the diver moved 0.08 m (breathing) and all 8 schools and 12 animals nearby kept moving; 73 of 74 animals change between dives, 1 to 7 absent, 0 paths through rock; keys turn with no jump over 0.14 degrees per picture; a school's speed ranged from half to twice its average. <code>tests/solid.py</code> still 0 problems.	Kept

#	Version	Commit ID	Date	Commit name	Detailed description	Status
21	none	ab9a62a	25 Sep 2026, 23:56	Describe v1.4; start the report after every fix docs: describe v1.4; a report after every fix; Claude's notes	What changed: Hasib's new rule: after every fix, a PDF report of what is on the website and what to do next, and a notes file Claude keeps for itself. docs/make_report.py writes docs/reports/report-v1.4.pdf ; docs/claude-notes.md holds Claude's notes; the page style and PDF printing moved into docs/pdf_tools.py , shared by both PDF scripts. CLAUDE.md and README describe the v1.4 parts. Files: - New: docs/make_report.py , docs/pdf_tools.py , docs/claude-notes.md , docs/reports/report-v1.4.pdf , docs/reports/img/ - Changed: CLAUDE.md , README.md , docs/make_git_tracking.py State of the dive: Same as the commit before. Checks: Report opened and read through; no em dashes.	Kept
22	none	8aebc89	25 Sep 2026, 23:56	Set the version number to 1.4.0 release: set the version to 1.4.0	What changed: The last step on the branch before merging: package.json says 1.4.0. Files: package.json State of the dive: Same as the commit before. Checks: None needed.	Kept
23	v1.4	d8c7364	25 Sep 2026, 23:56	Release v1.4: merge the branch into main v1.4: a smooth start, a living pause, a new dive every time	What changed: The merge commit that brings the four commits of feature/v1.4-feel into main , tagged v1.4 . The planned animal behaviour moves to v1.5, because these fixes came first (a number always means one thing). Files: Everything changed on the branch (the four rows above it). State of the dive: v1.4: smooth start, living pause, a new dive every time, smooth keys, real fish speeds. Checks: All tests passed on the branch before merging.	Kept
24	none	b4b1e65	25 Sep 2026, 23:58	Update this guide for v1.4 docs: update the tracking guide for v1.4	What changed: New rows, the start-of-dive chart, and the plan for v1.5 and later. Files: docs/git-tracking.pdf , docs/make_git_tracking.py State of the dive: Same as v1.4. Checks: PDF opened and read through.	Kept

#	Version	Commit ID	Date	Commit name	Detailed description	Status
25	none	3f940fc	26 Sep 2026, 00:47	Smooth zoom, level turning, side panel, home button, animals at new depths feat: smooth zoom, level turning, a side panel, a home button, animals at new depths each dive	What changed: Hasib's five points after trying v1.4. Zoom: each press now steps smoothly 1x, 1.3x, 1.6x, 2x, 2.5x and back down (no jump from the top to 1x); holding zooms smoothly; in deep water the limit was 1.2x (a press often did nothing), now 1.5x to 2.5x; small corals stay drawn when zoomed. Turning: on steep parts of the dive the arrow keys spun the view in a circle, because turning followed the dive path's tilt; it is now always around the true vertical with a level horizon. Side panel: Pause/Play, Music and Zoom moved to a panel on the left edge, hidden until you hover (a handle opens it on phones). Home: Deep Drift at the top goes back to the start screen; the Restart button is gone; the end of the dive also returns there; the start screen explains the panel. Variety: each scripted animal now meets you anywhere within the depths where it really lives (one shared list), so a deep animal is never near the surface. Found while testing: swimming into the reef shelf's lip could lift you 3 m at once (the lip now stops you), and a big animal could shove you 3 m (big animals now nudge you gently first). Files: - New: <code>src/diver/zoom.js</code>, <code>src/ui/dock.js</code>, <code>src/life/depths.js</code>, <code>tests/controls.py</code> - Changed: <code>index.html</code>, <code>styles/main.css</code>, <code>main.js</code>, <code>camera.js</code>, <code>input.js</code>, <code>collision.js</code>, <code>autoplay.js</code>, <code>panels.js</code>, <code>motion.js</code>, <code>variety.js</code>, <code>passers.js</code>, <code>school.js</code>, <code>touch.js</code>, <code>cast.js</code>, <code>extras.js</code>, <code>culling.js</code>, <code>wet.js</code>, <code>uniforms.js</code>, <code>debug.js</code>, <code>tests</code> State of the dive: New controls layout, home button, smooth zoom, level turning, animals met at new depths each dive. Checks: <code>tests/controls.py</code>: zoom 1.3, 1.6, 2, 2.5, 2, 1.6, 1.3, 1; horizon level after turning on a 43-degree slope; panel hidden until hover; home works; 39 animals never met outside their depths over 6 dives. Solid, life, glide, menu, live and real-graphics startup tests pass.	Kept

#	Version	Commit ID	Date	Commit name	Detailed description	Status
26	none	3efc866	26 Sep 2026, 02:08	Animals and fish stay in the water fix: animals and fish stay in the water; a faster controls test	What changed: Found by checking each animal's own depth (not the diver's): with the new meeting moments near the surface, the dolphins and the turtle could drift up out of the water, up to 10 m above it. Scripted animals, visitors and school fish are now kept below the surface. The controls test now judges each animal by its own depth and runs its zoom and turning checks without drawing (much faster). Files: motion.js , passers.js , school.js , debug.js , tests/controls.py State of the dive: Same as the commit before, with every animal in the water. Checks: controls.py: 0 animals met outside their depths (and none above the water) over 6 dives; solid, life and live tests pass.	Kept
27	none	e41dada	26 Sep 2026, 02:08	Describe v1.5; report v1.5; notes docs: describe v1.5, report and notes	What changed: CLAUDE.md and README describe the new controls, zoom, level turning and depth list; docs/reports/report-v1.5.pdf shows what is on the website now and what is next; Claude's notes updated. Files: CLAUDE.md , README.md , docs/claude-notes.md , docs/make_report.py , docs/reports/report-v1.5.pdf , docs/reports/img/v1.5-controls.jpg State of the dive: Same as the commit before. Checks: Report opened and read through; no em dashes.	Kept
28	none	502d662	26 Sep 2026, 02:08	Set the version number to 1.5.0 release: set the version to 1.5.0	What changed: The last step on the branch before merging: package.json says 1.5.0. Files: package.json State of the dive: Same as the commit before. Checks: None needed.	Kept

#	Version	Commit ID	Date	Commit name	Detailed description	Status
29	v1.5	d7ec890	26 Sep 2026, 02:08	Release v1.5: merge the branch into main v1.5: smooth zoom, level turning, a side panel and a home button	What changed: The merge commit that brings the four commits of <code>feature/v1.5-controls</code> into <code>main</code>, tagged <code>v1.5</code>. Animal behaviour moves to v1.6 and real models to v1.7 or later. Files: Everything changed on the branch (the four rows above it). State of the dive: v1.5: new controls and home button, smooth zoom, level turning, animals at new depths each dive. Checks: All tests passed on the branch before merging.	Kept
30	none	d92f0b9	26 Sep 2026, 02:09	Update this guide for v1.5 docs: update the tracking guide for v1.5	What changed: New rows and the plan for v1.6 and later. Files: <code>docs/git-tracking.pdf</code>, <code>docs/make_git_tracking.py</code> State of the dive: Same as v1.5. Checks: PDF opened and read through.	Kept
31	none	e59b8e3	26 Sep 2026, 04:52	Recenter view moves into the side panel ui: move Recenter view into the side panel	What changed: Hasib's first change made by himself, as a lesson: the Recenter view button moved from the top row into the side panel on the left edge, with its hidden label and the start-screen hint updated, and the phone Menu no longer closing for it. Files: <code>index.html</code>, <code>src/ui/panels.js</code> State of the dive: Recenter view sits in the side panel. Checks: Tried in the browser; menu and live tests pass.	Kept
32	none	7e7028c	26 Sep 2026, 04:52	A quiet home screen audio: music is off on the home screen and comes back on Begin if it was playing	What changed: Going back to the start screen stops the music; pressing Begin brings it back only if it was playing before. Files: <code>src/audio/music.js</code>, <code>src/ui/playback.js</code> State of the dive: Music stops at home. Checks: Checked: on, home (off), Begin (on); off before home stays off.	Kept

#	Version	Commit ID	Date	Commit name	Detailed description	Status
33	none	abb9c0e	26 Sep 2026, 04:52	Faster return visits; measuring loading build: cache the 3D library, fish model and fonts for return visits; add a loading-speed test	What changed: Measured first-visit loading on a slowed connection with the files compressed like Cloudflare does: 1.2 MB, about 3 s to download at 9 Mbit/s; the real wait is building the world (about 3 s on Hasib's laptop). A list of early downloads was tried and gave no gain, so it was left out. Kept: cache rules (<code>_headers</code>) so returning visitors keep the 3D library, the fish model and the fonts for a day. Files: <code>tools/build.py</code> , new <code>tests/load.py</code> , <code>tests/cloudlike_server.mjs</code> State of the dive: Same dive; return visits load faster. Checks: load.py measured before and after.	Kept
34	none	68cd156	26 Sep 2026, 04:57	A clean start screen that appears at once ui: a clean start screen that appears at once, with a progress bar	What changed: The long paragraph and the controls box are gone. The start screen shows a small line (An interactive ocean dive), the title, the subtitle Descend from sunlight into the deepest dark on Earth., three short hints, and Begin with a slim progress bar. It is written in the page itself, so it appears before any code runs. Nothing else shows behind it. Files: <code>index.html</code> , <code>styles/main.css</code> , <code>src/main.js</code> , <code>src/config.js</code> , <code>src/ui/playback.js</code> State of the dive: New start screen. Checks: Pictures while loading, ready, in the dive and home again; all tests pass.	Kept
35	none	931c81c	26 Sep 2026, 04:59	A commit log docs: describe v1.5.1 and add a commit log	What changed: <code>docs/commit-log.md</code> lists every commit and whether it is uploaded to GitHub and live; <code>tools/commit_log.py</code> rebuilds the table from git. <code>CLAUDE.md</code> describes publishing and the new rules. Files: <code>CLAUDE.md</code> , <code>README.md</code> , <code>docs/claude-notes.md</code> , <code>docs/make_report.py</code> , <code>docs/commit-log.md</code> , <code>tools/commit_log.py</code> State of the dive: Same as the commit before. Checks: Read through.	Kept

#	Version	Commit ID	Date	Commit name	Detailed description	Status
36	none	1acbe68	26 Sep 2026, 04:59	Set the version number to 1.5.1 release: set the version to 1.5.1	What changed: The last step on the branch before merging: <code>package.json</code> says 1.5.1. Small improvements get the third number. Files: <code>package.json</code> State of the dive: Same as the commit before. Checks: None needed.	Kept
37	v1.5.1	1a9359f	26 Sep 2026, 04:59	Release v1.5.1: merge the branch into main v1.5.1: a clean start screen, Recenter view in the side panel, a quiet home screen	What changed: The merge commit that brings the six commits of <code>feature/start-screen</code> into <code>main</code>, tagged <code>v1.5.1</code>. Files: Everything changed on the branch (the six rows above it). State of the dive: v1.5.1: new start screen, Recenter in the side panel, quiet home screen. Checks: All tests passed on the branch before merging.	Kept
38	none	7c1a59a	26 Sep 2026, 05:00	Update this guide and the commit log for v1.5.1 docs: update the tracking guide and commit log for v1.5.1	What changed: New rows for v1.5.1. Files: <code>docs/git-tracking.pdf</code>, <code>docs/make_git_tracking.py</code>, <code>docs/commit-log.md</code> State of the dive: Same as v1.5.1. Checks: PDF opened and read through.	Kept
39	none	f376666	26 Sep 2026, 23:38	Side panel: swipes on the left edge turn you again fix: the closed side panel no longer blocks swipes, and touch opens and closes it properly	What changed: Hasib found that on a phone (and with a mouse) a swipe starting on the hidden side panel did not turn the view. The panel's invisible box covered the left edge and caught the touch. Now only the small handle catches touches. Also, hover only counts on screens with a real mouse (a tap left it stuck on, so the handle needed two taps), and only keyboard focus keeps the panel open. Files: <code>styles/main.css</code> <code>tests/controls.py</code>: new checks for swipes, hover and touch State of the dive: Swipes turn the view everywhere; the panel still opens by hover (mouse) or the handle (touch). Checks: controls, ui and live tests pass. Touch was tried in the test browser only, not yet on a real phone.	Kept

#	Version	Commit ID	Date	Commit name	Detailed description	Status
40	none	b233511	26 Sep 2026, 23:38	Nothing leaves the water; jellyfish stay put; the manta keeps clear fix: nothing leaves the water; jellyfish hang in place; the manta keeps clear of the diver	What changed: Hasib saw jellyfish rise out of the water like parachutes, and a manta collide with him. Jellyfish now hang and wander around their own spot (4 at the reef instead of 9, kept a few metres under the surface). Every animal is held under the surface by its size, breath bubbles vanish when they reach it, and floating specks are hidden above it. The manta's hit shape now matches the drawn animal (about 5.9 m across, disc ahead of the centre), it turns away 4 m sooner, and big visitors cross well ahead of the diver. Files: - src/life/surface.js (new), jelly.js , cast.js , extras.js , passers.js , touch.js - src/diver/bubbles.js , src/engine/particles.js , src/main.js , src/debug.js - tests/surface.py (new) State of the dive: Nothing shows above the surface; jellyfish stay within about 2 m of their spot. Checks: New surface test passes, and fails on the old code (jellyfish drifted 44 m, a bubble rose 3.85 m into the air). controls and life tests pass. The solid test sometimes shows a turtle appearing on screen; the old code does the same.	Kept
41	none	2153ae5	26 Sep 2026, 23:39	Update this guide, the notes and the commit log docs: track the side panel and surface fixes	What changed: Rows for the two fixes above. Files: docs/git-tracking.pdf , docs/make_git_tracking.py , docs/commit-log.md , docs/claude-notes.md State of the dive: Same as the fixes above. Checks: PDF made from the real commits.	Kept

#	Version	Commit ID	Date	Commit name	Detailed description	Status
42	none	0de4d1b	27 Sep 2026, 03:09	Bubbles dissolve under the surface fix: bubbles slow down and dissolve under the surface instead of popping	What changed: Hasib saw breath bubbles seem to rise out of the water when looking up from a few metres down. Bubbles used to vanish at full size on touching the surface. Now they slow to a third of their speed over the last 1.5 m, shrink smoothly, fan out a little sideways, and old bubbles fade instead of popping. Files: - src/diver/bubbles.js - tests/surface.py : fails if a bubble is still big near the surface State of the dive: Bubbles never look like they leave the water. Checks: surface, life, controls tests pass. Hasib confirmed the bubble problem was solved.	Kept
43	none	22e206d	27 Sep 2026, 03:09	The surface and the sunbeams look like real water light feat: the water surface and sunbeams look like real water light	What changed: Hasib said the surface looked like sky, then like silk, and the sunbeams like pipes. After reading how light really enters the sea (waves act as lenses and make curved sheets of light, sharp near the top and blurrier and fainter deeper), the surface seen from below is now a web of moving light lines with a sun glare and a silvery edge. Beams lean at the refracted sun angle (about 23 degrees), are all parallel, are brightest at the surface and fade within the top 100 m, and are streaks of light and shadow tied to the water instead of plain tubes. Two bugs fixed: the sheets leaned in random directions and their brightness was upside down. Files: - src/engine/sky.js - src/engine/environment.js State of the dive: A rippled water ceiling; parallel, slanted, streaky sunbeams in the top tens of metres; plain diffuse blue deeper. Checks: startup, surface, ui, controls, life tests pass, no shaders built late. Looked at screenshots at 3, 14, 40 and 120 m. Not measured on the Intel laptop.	Kept
44	none	e9e7579	27 Sep 2026, 03:09	A darker start screen ui: a darker start screen so all of its text can be read	What changed: The small line 'An interactive ocean dive' could not be read over the bright sea. The backdrop is darker and the small text has a soft shadow. Files: styles/main.css State of the dive: All lines of the start screen read clearly on desktop and phone. Checks: Screenshots of desktop and phone.	Kept

#	Version	Commit ID	Date	Commit name	Detailed description	Status
45	none	f7eeef4	27 Sep 2026, 03:09	Update this guide, the notes and the commit log docs: track the surface, sunbeam and start screen changes	What changed: Rows for the three changes above. Files: docs/git-tracking.pdf , docs/make_git_tracking.py , docs/commit-log.md , docs/claude-notes.md State of the dive: Same as the changes above. Checks: PDF made from the real commits.	Kept
46	none	47a052e	27 Sep 2026, 03:46	A faster first visit: smaller fish pictures, fetched early perf: smaller fish pictures, fetched while the code is still arriving	What changed: Hasib asked for a more efficient first loading. Measured first: on his laptop Begin is ready about 3.3 s after the code starts, and the fish was 43 percent of the download and was only requested after all the code had arrived. The fish's three 1024 pixel pictures (518 KB of text inside a JSON file) are now 512 pixel WebP files (105 KB in all, the same to the eye at twice the real size), and index.html tells the browser to start fetching the fish files at once, side by side with the code. In a slowed-network test (9 Mbit/s, 150 ms) the fish step went from 760 ms to 10 ms and the first-visit download from 1,177 KB to 904 KB. On a local run there is no difference, because there is no network delay. Files: - assets/barra_color.webp, barra_normal.webp, barra_orm.webp (new); assets/barra_tex.json removed - src/life/barramundi.js , index.html - tools/fish-model/shrink_textures.py (new) and the original pictures kept in tools/fish-model/ - tests/shot.py , tests/cloudlike_server.mjs : know the .webp type State of the dive: Same look, less to download, and the fish arrives with the code. Checks: startup, ui, controls, live and surface tests pass, no shaders built late. Real-internet speed not yet tested (waiting for the Cloudflare preview).	Kept

#	Version	Commit ID	Date	Commit name	Detailed description	Status
47	none	Added at the next update (see section 3)	this commit	Update the guide, the notes and the commit log docs: track the faster opening change	What changed: A row for the faster opening change, and the loading measurements in the notes. Files: docs/git-tracking.pdf , docs/make_git_tracking.py , docs/commit-log.md , docs/claude-notes.md State of the dive: Same as the change above. Checks: PDF made from the real commits.	Kept

Planned (not saved yet)

v1.1 (the realism work), v1.2 (the continuous dive), v1.3 (the solid world and faster start) v1.4 (smooth start, living pause, variety) and v1.5 (controls, zoom, level turning, home button) are done. After every fix there is also a report in docs/reports. What is left is below. Rows move into the table above when they are committed.

Version	Change	What it will do
v1.6	Animal behaviour	Curious and startled school fish, predators chasing schools, hidden animals (day octopus with ink, flounder, scorpionfish, garden eels), deep-sea light displays, feeding at the vents and the whale skeleton, animals steering around corals.
v1.7+	Real 3D models	In small batches from Sketchfab, each with Hasib's OK on its licence and a credit in the page.
none	Lighter reef	Simpler far corals, so laptops like Hasib's can draw the reef at full sharpness.
none	Phone check	Try the dive on a real phone: speed, the side panel, motion look (gyro), and the glide. Needs Hasib's phone.
none	Publish	First public version on GitHub Pages (free), after local testing. Needs a GitHub account.

7. Before and after pictures

Taken by the test script with the same settings, at the same moments of the dive. The test window counts as a small screen, so these show the lighter phone-level detail.



v1.5 on Hasib's laptop: the start screen with the new hint, the side panel closed and open, zoomed in to 2.5x.

Start of the dive on Hasib's laptop (Intel UHD graphics, 1536x864 at 125%): v1.3 (grey) and v1.4 (blue)

Longest hitch in the first 10 to 12 s of the dive (shorter is better)




Time for one picture of the busy reef (full sharpness 1.25) (shorter is better)



Loading screen: longest freeze (shorter is better)



v1.4, the start of the dive on Hasib's laptop (Intel UHD graphics, 1536x864 at 125%): v1.3 and v1.4.



v1.3, solid world. The diver is sent straight into the whale skeleton on the abyssal plain. Left, v1.2: the camera ends up inside the rib cage. Right, v1.3: the diver is stopped just above the bones.

Opening the page: v1.2 (grey) and v1.3 (blue), measured in the test browser (software graphics, slower than a real computer)

Triangles drawn in the first view (fewer is lighter)



Time until Begin can be pressed (shorter is better)



Pictures drawn in the first 6 s of the dive (more is smoother)



v1.3, opening the page, measured in the test browser (software graphics, so all numbers are slower than on a real computer; compare the bars, not the numbers).



v1.1 (before v1.2): six separate places, with a fade to black between the vents, the wreck and the trench.



v1.2: one continuous dive. Left to right, top to bottom: reef 11 m and 54 m, reef drop-off 155 m, twilight 560 m (hatchetfish), midnight 1,120 m (vampire squid) and 1,450 m (anglerfish), vents 1,580 m, volcano slope 2,270 and 3,440 m, abyssal plain 4,840 m, wreck 4,860 m, whale skeleton 5,185 m, trench 6,300 and 8,275 m, Challenger Deep 10,890 m.



Before (v1.0). Top: reef at 8, 32 and 52 m. Middle: midnight zone (the anglerfish should be here), vents, wreck. Bottom: wreck, trench, trench.



After (v1.1), at the same moments of the dive (the anglerfish and trench shots are a few seconds later, when the animals pass).

8. Words used in this guide

Repository (repo)	The project folder plus its <code>.git</code> history.
Commit	One saved snapshot of the whole project, with a message.
Commit ID (hash)	The fingerprint name of a commit, like <code>7929f37</code> .
Stage / staging area	The waiting list of changes for the next commit.
Branch	A moving name for the newest commit of a line of work: <code>main</code> for releases, a side branch per new version.
Merge	Bringing a side branch into <code>main</code> . The merge commit has two parents: the last commit on each line.
Release	A tested version merged into <code>main</code> and given a tag, like <code>v1.2</code> .
Tag	A fixed name for one commit, used for version numbers.
HEAD	The commit the working folder is currently based on.
Revert	Undo a commit by adding its opposite as a new commit.
Remote	A copy of the repository somewhere else, like GitHub. We have none yet.